


ME14

Technical Specification



Facility

- ✔ Capacity for 350+ Racks
- ✔ 18-24 rack suites for more privacy and exclusivity
- ✔ Secure docking area for loading and delivery
- ✔ Scalability of infrastructure
- ✔ On-site offices, meeting rooms and restaurant

Security

- ✔ ISO 27001 certified
- ✔ Security manned by in-house team 24/7/365
- ✔ SEAP 3 rated perimeter fencing
- ✔ Air lock gates on perimeter and turnstiles into data halls
- ✔ PIN, photographic and card combination access
- ✔ Infrared CCTV with motion detectors linked directly to the Building Management Systems
- ✔ Individual security options: in-rack CCTV accessible from your network, mobile devices, PC etc.

Cooling

- ✔ Average supply temperature: 19°C to 26°C ± 2°C
- ✔ Award Winning Fresh Air Cooling System
- ✔ 2N resilient Evaporative Cooling System
- ✔ Moisture Detection and Control Sensors
- ✔ Annualised PUE of 1.2 displayed live online

Monitoring

- ✔ Full system monitoring to NOC and automated self-diagnostics
- ✔ Network Status and Loading
- ✔ Individual rack power metering
- ✔ Customer portal
- ✔ Argonite Suppression Systems
- ✔ AHU Environmental Conditions
- ✔ Very Early Smoke Detection Apparatus (VESDA)
- ✔ 1 Hour Fire Rated Data Rooms

Connectivity

- ✔ Six entry points into the facility
- ✔ Carrier agnostic
- ✔ Managed layer 2 network
- ✔ Dark Fibre Network
- ✔ Fully Multi-homed and highly resilient IP Transit service under our own ASN 50300

Power

- ✔ A 100% Uptime Record
- ✔ True 2N UPS Dual Path Resilience
- ✔ 64 Amps (15KW) of fully redundant power per rack available
- ✔ Triple network power grid feeds
- ✔ Automatically activated diesel generators with priority refuelling contracts
- ✔ Bi-weekly generator testing under full load Dual feed or diverse dual feed